Abstract Notification dated the 16th December 1939.

Attention of the public is invited to this Office Notification, dated the 16th December 1939, published on pages 2568-2569 of Part VI of the *Mysore Gazette*, dated 21st December 1939, calling for sealed tenders for the supply of Elephant accoutrements to this Division.

M. A. MUTHANNA,
District Forest Officer.

SAGAR FOREST DIVISION.

Abstract Notification dated 12th December 1939.

The attention of the public is invited to the detailed notification published on page 2570, Part VI of the *Mysore Gazette*, dated 21st December 1939, regarding the sale of the right of collection and removal of canes from the several State Forests of this Division, during the year 1939-40.

Sagar Range ... 8th January 1940.
Nagar Range ... 10th January 1940.

N. VENKATARAMAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 13—14th December 1939.

The attention of the public is invited to the notification calling for tenders for the work of constructing 1st stage drains in Maddur town, published on pages 2573-2574 of Part VI of the *Mysore Gazette*, dated 21st December 1939.

The last date of receiving tenders is fixed on 4th January 1940.

Notification dated 16th December 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 12th January 1940, for providing Sanitary and Laboratory fittings at the Extension for completing the Northern Wing of the Medical College, at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer on payment of a fee of annas four for each form. No tender not submitted in the prescribed form will be accepted. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 125 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for providing Sanitary and Laboratory fittings at the Extension for completing the Northern Wing of the Medical College at Mysore," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Abstract of approximate quantities for the work of providing Sanitary and Laboratory fittings at the extension for completing the Northern Wing of the Medical College, Mysore.

No.	Items of work	Unit	Quantity	Rate to be quoted
	Water and Gas connections.			Rs. a. p.
1	Removing and refixing existing sinks including disconnection of brackets, water and waste pipes, plugs to disconnected pipes, etc., complete	No.	12	
2	Removing and refixing gas taps, swan necked cocks and water taps including removing all connected pipes with extra plugs, new fittings and lead clamps, etc., complete	No.	34	
3	Removing and refixing bigger sinks with waste connections painting, etc., repairs to wall and floor	No.	3	
4	Providing 1¼″ lead pipes to replace worn out ones while removing bending and fixing with wiped solder joints and making caps to suit outlets of sinks	,,	3	
5	Providing 2″ G. I. pipe for outlet of bigger sinks including laying with necessary fittings	R.ft.	24	
6	Providing 1½″ G. I. Main with all fittings including earthwork excavation laying and jointing, refilling, etc., complete	,,	180	
7	Do do 1″ do do	,,	180	
8	Providing ¾″ and ½″ G. I. pipes with fittings for W. C. Lavatory basin and tap connections upto outside wall	No.	3	
9	Providing 1½″ Black gas pipe for main including earthwork excavation laying and jointing with necessary fittings and refalling, etc. complete	R.ft.	160	
10	Do do 1″ inside do	,,	140	
11	Do do ¾″ and ½″ do	,,	100	
12	Connection with the existing gas main with necessary fittings removing and re-jointing, etc., complete	,, No.	1	
13	Providing and fixing 1½″ full way gate valve	,,	1	
14	Do 1½″ G. M. Gland cock	,,	1	
15	Do ½″ N. P. stop cock	,,	2	
16	Do ½″ N. P. big cock	,,	1	
17	Constructing road box cistern for gate valve and Gland cock including cost of C. I. road boxes	,,	2	
18	Making cement concrete channel with 3″ for sides and cement plastering above channel pipes and making rim on both sides to rest C. I. grating of 10″ wide including cutting floor	R.ft.	30	
19	Do do 7″ do do	,,	100	
20	Do do 3″ do for gas and waste pipes	,,	120	
21	Providing and fixing in cement mortar 6″ S. W. channel pipes including cut pieces and pointing the joints in cement	,,	30	
22	Do do 4″ S. W. channels do	,,	100	
23	Encasing with cement concrete on both sides of C. I. grating and cement plastering mixed with red chre and fixing Grating without shaking edges 10″ wide including cutting to required size	,,	30	
24	Do do 7″ do do	,,	100	
25	Do do 3″ do do	,,	120	
26	Cutting basement slabs and chiselling for 2″ G. I. waste	No.	12	
27	Cornice bore and re-doing after fixing pipes	,,	2	
	Soil and Waste Fittings.			
1	Fixing W. C. and Lavatory basin complete	No.	2	
2	Fixing accessories	,,	3	
3	Providing and fixing 4″ C. I. soil pipe with specials including necessary scaffolding	,, R.ft.	60	
4	Do do 3″ C. I. waste pipe do	,,	12	

No.	Items of work	Unit	Quantity	Rate to be quoted
				Rs. a. p.
5	Providing and fixing 4″ C. I. trap in cement	No.	1	
6	Constructing cistern in cement concrete providing and fixing 6″ diameter N. P. Grating	,,	1	
7	Providing 1¼″ lead pipe with wiped solder joints including bend and fixing, etc.	,,	1	
8	Do do ¾″ and ½″ do		3	
9	Constructing ground sink in cement concrete and cement plastering mixed with red ochre	,,	1	
10	Painting fittings and waste pipes		18	
	Drainage Arrangements.			
1	Providing 4″ S. W. pipe, laying and jointing including earthwork excavation, refilling and tamping, etc., complete	R.ft.	180	
2	Providing and fixing 4″ S. W. bend ordinary	No.	4	
3	Do 4″ S. W. cleaning door bend	,,	4	
4	Do 6″ S. W. bend ordinary	,,	1	
5	Do 6″ S. W. cleaning door bend	,,	1	
6	Providing 6″×4″ S. W. Gully trap with C. I. grating	,,	6	
7	Constructing cistern in cement, mortar and providing and fixing 12″×10″ C.I. hinged frame and cover	,,	6	
8	Encasing S. W. bend and pipes outside with brick in cement, and cement plastering	,,	4	
9	Constructing inspection chamber with 24″×18″ C. I. ring and cover upto 3′ depth	,,	3	
10	Constructing manhole as per design with 21″ dia. C. I. manhole cover and frame upto 8′ depth	,,	1	
11	Do do do upto 4½′ depth	,,	1	
12	Connection with the existing manhole and making good	,,	3	
13	Providing fixing 4″ zinc cowl	,,	1	
14	Stone wall bore (big stone) and redoing in cement	,,	8	

List of materials to be indented for, for the work of providing Sanitary and Laboratory fittings at the extension for completing the Northern Wing of the Medical College, Mysore.

No.	Materials	Unit	Quantity	Rate to be quoted
				Rs. a. p.
1	White porcelain English water closet with 3 gallon C. I. flushing cistern with telescopic flush pipe chain and pull complete set	No.	1	
2	White porcelain Lavatory basin 25″×18″ size overall with one cold cock at centre with waste union, chain and plug and one pair of C. I. brackets complete set	,,	1	
3	24″×18″ mirror, enclosed in white wood rectangular frame	,,	1	
4	N. P. Towel rail 1″ dia. and 24″ long with N. P. brackets	,,	1	
5	White porcelain toilet paper holder with paper	,,	1	

K. S. HUTCHA RAO,
Sanitary Engineer.

MEDICAL DEPARTMENT.

KRISHNARAJENDRA HOSPITAL, MYSORE.

Abstract Notice, dated 7th December 1939.

Sealed tenders for the supply of bedding and clothing required for the use of the Krishnarajendra Hospital for the year 1939-40 will be received by the undersigned on Monday the 15th January 1940 at 11 A.M. at the Krishnarajendra Hospital, Mysore.

For further particulars, *vide Mysore Gazette* of 14th December 1939, Part VI, pages 2525-2526.

H. S. SAMPANGIRAMAIAH,
Secretary.